

工程审定概算表

工程名称：隆惠村水城路两侧退水沟、排污沟整治项目（初步设计）

序号	工程或项目名称	工程量 (m ²)	概算价值(万元)				合计 (万元)	备注
			土建	设备费	安装工程	其它费用		
一	工程费用		318.45				318.45	
1	裸露土地种植工程		291.78				291.78	
1.1	清理杂草	110104 m ²	55.05				55.05	
1.2	拆除及余土清运 5km	600m ³	1.80				1.80	
1.3	盐碱土及淤泥清运 5km	13450m ³	40.35				40.35	
1.4	回填种植土	55052m ³	192.68				192.68	
1.5	场地平整	18699 m ²	1.90				1.90	
2	生活污水管道工程		26.67				26.67	
2.1	钢筋砼管 D400 (II级)	438m	20.27				20.27	
2.2	钢筋砼检查井	15座	5.25				5.25	
2.3	钢筋砼化粪池 10m ³	1座	1.15				1.15	
二	其它费用					22.58	22.58	
1	建设单位管理费 1%					3.18	3.18	
2	勘察、测量费 0.5%					1.59	1.59	
3	设计费 2.5%					7.96	7.96	
4	工程监理费 1.5%					4.77	4.77	
5	招投标服务费 0.4%					1.27	1.27	
6	预算编制及审查费 0.6%					1.91	1.91	
7	林地评估费					0.50	0.50	
8	水土保持方案编制费					0.60	0.60	
9	环评费					0.80	0.80	
三	预备费 3% (一、二项之和)					10.23	10.23	
四	合计		318.45			32.81	351.26	